

SECTION 01 55 26
TRAFFIC CONTROL

PART 1 - GENERAL

1.1 DESCRIPTION

- A. This Specification includes the general description of the “TRAFFIC CONTROL” and the requirements of that plan. This specification applies to the furnishing of all labor, equipment, and materials and in performing all operations in connection with the “TRAFFIC CONTROL” in accordance with the plans and these specifications.

1.2 MEASUREMENT AND PAYMENT

The work and materials as prescribed by this item will be paid on the following schedule:

- A. 50% of the bid value shall be paid when the traffic control plan is fully implemented, and all of the initial traffic control devices have been installed and are in working order.
- B. 25% of the value will be prorated for the installation and maintenance of traffic control devices during the course of construction as a percent of the total contract value.
- C. 25% will be paid at the completion of construction and all traffic control devices are removed from the site.

1.3 SUBMITTALS

- A. The contractor shall submit a “TRAFFIC CONTROL PLAN” or modifications to the plan provided in the construction documents prior to commencing construction. All plans must be in accordance with the Texas Manual of Uniform Traffic Control Devices requirements. No plan may be implemented until approved by the Engineer.

PART 2 – PRODUCTS

N/A

PART 3 – EXECUTION

3.1 CONSTRUCTION METHODS

- A. The “TRAFFIC CONTROL PLAN” and the installation of all devices should be continuously reviewed and updated to reflect the current stage of construction. The inspector may review minor changes; the engineer shall review major changes. The construction foreman shall provide the current “TRAFFIC CONTROL PLAN” to the inspector upon request on the site at any time during the construction of the project.

END OF SECTION