



NOTES:

- 1. FURNISH AS SHOWN ON PLANS AND ON ALL VALVE SIGN POSTS.
- 2. SIGNS TO BE CONSTRUCTED FROM 20 GA. STEEL BAKED ON ENAMEL FINISH. FURNISH ONE WARNING AND ONE VALVE SIGN AND ONE POST FOR EACH VALVE INSTALLED AND AT OTHER LOCATIONS AS SHOWN ON PLANS. FURNISH SAME NUMBER OF REPLACEMENT SIGNS AS FOR EACH INSTALLED (OMITTING VALVE NUMBER ON VALVE SIGN BLANK) (NOT A SEPARATE PAY ITEM)



IN-LINE BLOW OFF ASSEMBLY

AUG. 2012

B/CS UNIFIED STANDARD DETAIL

DETAIL NO.

W3-01

